

BaseLine Item Detail					Ferreira Construction Co. Inc.		Joseph M. Sanzari, Inc.	
Item No.	Unit Code	Qty	UOM	Description	Unit Price	Line Total	Unit Price	Line Total
1	104-0001		1.00 L.S.	Construction Layout	\$92,753.00	\$92,753.00	\$200,000.00	\$200,000.00
2	104-0002		1.00 L.S.	Mobilization	\$500,000.00	\$500,000.00	\$1,250,000.00	\$1,250,000.00
3	107-0001		1.00 L.S.	Progress Schedule	\$8,000.00	\$8,000.00	\$32,000.00	\$32,000.00
4	108-0001	10,000.00	USD	Fuel Price Adjustment (No-Bid)	\$1.00	\$10,000.00	\$1.00	\$10,000.00
5	201-0001		1.00 Acre	Clearing and Grubbing	\$10,000.00	\$10,000.00	\$45,000.00	\$45,000.00
6	202-0002		200.00 C.Y.	Roadway Excavation, Earth	\$100.00	\$20,000.00	\$185.00	\$37,000.00
7	202-0009	15,000.00	USD	Environmental Testing for Unsuitable and Excess Materials (No-Bid)	\$1.00	\$15,000.00	\$1.00	\$15,000.00
8	203-0002		63.00 C.Y.	Embankment, Grade A	\$285.00	\$17,955.00	\$190.00	\$11,970.00
9	205-0001		5.00 C.Y.	Foundation Excavation	\$100.00	\$500.00	\$700.00	\$3,500.00
10	207-0001		32.00 Ton	Riprap Stone Slope Protection, 12in Thick, (D50=6in)	\$850.00	\$27,200.00	\$500.00	\$16,000.00
11	207-0004		10.00 Ton	RipRap Stone Aprons, 12in Thick(D50=6in)	\$1,200.00	\$12,000.00	\$200.00	\$2,000.00
12	208-0007		3,008.00 L.F.	Silt Fence	\$20.00	\$60,160.00	\$10.00	\$30,080.00
13	208-0022		7.00 Each	Inlet Filter, Type 2	\$500.00	\$3,500.00	\$1,010.00	\$7,070.00
14	208-0024		54.00 Ton	Construction Driveway	\$400.00	\$21,600.00	\$331.00	\$17,874.00
15	208-N0002		2.00 Each	Sediment Control Bags	\$750.00	\$1,500.00	\$1,740.00	\$3,480.00
16	301-0002		356.00 S.Y.	Aggregate Base Course, 6in Thick	\$200.00	\$71,200.00	\$38.00	\$13,528.00
17	302-0001		724.00 Ton	Hot Mix Asphalt 19M 76 Intermediate Course	\$185.00	\$133,940.00	\$286.00	\$207,064.00
18	302-0002		3,826.00 Ton	Hot Mix Asphalt 12.5M76 Surface Course	\$250.00	\$956,500.00	\$1,150.00	\$4,399,900.00
19	302-0003		461.00 Ton	Hot Mix Asphalt 19M64 Intermediate Course	\$140.00	\$64,540.00	\$275.00	\$126,775.00
20	302-0004		127.00 Ton	Hot Mix Asphalt 25M64 Base Course	\$310.00	\$39,370.00	\$180.00	\$22,860.00
21	302-0062		9,000.00 S.Y.	Membrane Waterproofing	\$25.00	\$225,000.00	\$25.00	\$225,000.00
22	302-0063		5,000.00 USD	Asphalt Price Adjustment (No-Bid)	\$1.00	\$5,000.00	\$1.00	\$5,000.00
23	302-0065		5,000.00 L.F.	Cleaning Inside Shoulders	\$0.10	\$500.00	\$1.00	\$5,000.00
24	302-0066		5,000.00 L.F.	Cleaning Outside Shoulders	\$0.10	\$500.00	\$1.00	\$5,000.00
25	302-0068		100.00 Ton	High Performance Cold Patch	\$50.00	\$5,000.00	\$800.00	\$80,000.00
26	302-0071		7,978.00 L.F.	Polymerized Joint Adhesive	\$5.00	\$39,890.00	\$1.50	\$11,967.00
27	302-N0001		100.00 L.F.	Sealing Cracks in Bituminous Surface	\$0.10	\$10.00	\$8.70	\$870.00
28	302-N0002		12.00 Ton	Temporary Surfacing	\$850.00	\$10,200.00	\$3,000.00	\$36,000.00
29	302-N0007		1,352.00 GAL	Trackless Tack Coat	\$12.50	\$16,900.00	\$5.00	\$6,760.00
30	303-0001		746.00 S.Y.	Berm Surfacing, 3 Inches Thick	\$100.00	\$74,600.00	\$81.00	\$60,426.00
31	305-0001		370.00 S.Y.	Pavement Removal, 5in Depth	\$90.00	\$33,300.00	\$23.00	\$8,510.00
32	305-0006		5,163.00 S.Y.	Pavement Removal, 2in Depth	\$90.00	\$464,670.00	\$21.00	\$108,423.00
33	305-0031		9,193.00 S.Y.	Pavement Removal, Variable Depth	\$90.00	\$827,370.00	\$21.00	\$193,053.00
34	305-N0001		1,200.00 L.F.	Remove Existing Rumble Strip	\$40.00	\$48,000.00	\$35.00	\$42,000.00
35	306-0001		10,295.00 L.F.	Milled Rumble Strip	\$5.00	\$51,475.00	\$4.00	\$41,180.00
36	312-0001		190.00 L.F.	Sawing and Sealing Joints in Asphalt Concrete Overlay	\$50.00	\$9,500.00	\$10.00	\$1,900.00
37	401-0035		150.00 Each	Drill and Grout Reinforcement Bars	\$200.00	\$30,000.00	\$71.00	\$10,650.00
38	401-0067		331,108.00 LB	Reinforcement Steel, Epoxy Coated	\$0.75	\$248,331.00	\$2.00	\$662,216.00
39	401-0068		40.00 L.F.	Strip Seal Expansion Joints	\$1,200.00	\$48,000.00	\$1,400.00	\$56,000.00
40	403-0001		18,702.00 Each	Shear Connectors	\$2.50	\$46,755.00	\$7.50	\$140,265.00
41	408-0108		14.00 Each	Laminated Elastomeric Bearing, 7in X 16in, Fixed	\$12,000.00	\$168,000.00	\$11,000.00	\$154,000.00
42	408-0114		29.00 Each	Laminated Elastomeric Bearing 12in x 13in, Guided	\$12,000.00	\$348,000.00	\$13,000.00	\$377,000.00
43	408-0091		27.00 Each	Laminated Elastomeric Bearing, 11in X 12in, Guided	\$12,000.00	\$324,000.00	\$15,000.00	\$405,000.00
44	408-0118		5.00 Each	Laminated Elastomeric Bearing, 7in x 16in, Guided	\$12,000.00	\$60,000.00	\$14,500.00	\$72,500.00
45	408-0119		23.00 Each	Laminated Elastomeric Bearing, 9in X 23in, Guided	\$12,000.00	\$276,000.00	\$14,000.00	\$322,000.00
46	411-0001		5.00 Each	Temporary Storage and Recycling of Surface Preparation, Hazardous Waste, 55 Gallon Drum	\$1,000.00	\$5,000.00	\$1,000.00	\$5,000.00
47	411-N0001		5,518.00 S.F.	Painting Existing Steelwork	\$46.00	\$253,828.00	\$75.00	\$413,850.00
48	411-N0003		1.00 L.S.	Temporary Storage and Recycling/ Disposal of Hazardous Surface Preparation Waste	\$600.00	\$600.00	\$10,000.00	\$10,000.00
49	412-N0002		260.00 L.F.	Clean Bridge Drainage System	\$50.00	\$13,000.00	\$25.00	\$6,500.00
50	412-N0003		16.00 Each	Weld Existing Inlet Grate	\$2,000.00	\$32,000.00	\$1,220.00	\$19,520.00
51	413-0007		5.00 C.Y.	Underbridge Slope Fill Material	\$500.00	\$2,500.00	\$750.00	\$3,750.00
52	414-0003		1,680.00 L.F.	Bridge Railing	\$295.00	\$495,600.00	\$185.00	\$310,800.00
53	417-0004		400.00 S.Y.	Concrete Deck Replacement	\$800.00	\$320,000.00	\$900.00	\$360,000.00
54	417-0005		1,560.00 S.Y.	Concrete Deck Replacement With Catches	\$1,625.00	\$2,535,000.00	\$1,050.00	\$1,638,000.00
55	417-0008		304.00 Each	Reinforcement Bar Coupler	\$1.00	\$304.00	\$60.00	\$18,240.00
56	417-0009		8,174.00 S.Y.	Removal of Existing Surfacing	\$105.00	\$858,270.00	\$175.00	\$1,430,450.00
57	417-0016		7,967.00 S.F.	Spall Repair, Type 5	\$1.00	\$7,967.00	\$55.00	\$438,185.00
58	417-0017		50.00 S.F.	Spall Repair, Type 5A	\$125.00	\$6,250.00	\$125.00	\$6,250.00
59	417-0022		100.00 L.F.	Joint Seal Replacement	\$100.00	\$10,000.00	\$425.00	\$42,500.00

BaseLine Item Detail					Ferreira Construction Co. Inc.		Joseph M. Sanzari, Inc.	
Item No.	Unit Code	Qty	UOM	Description	Unit Price	Line Total	Unit Price	Line Total
60	417-0023	16.00	L.F.	Joint Reconstruction, Type 2A	\$850.00	\$13,600.00	\$550.00	\$8,800.00
61	417-0038	122.00	L.F.	Joint Seal Replacement, Type 75W	\$100.00	\$12,200.00	\$160.00	\$19,520.00
62	417-0044	22.00	L.F.	Joint Replacement, Type 1P	\$900.00	\$19,800.00	\$2,200.00	\$48,400.00
63	417-0046	90.00	L.F.	Joint Seal Replacement, Type 40W	\$100.00	\$9,000.00	\$130.00	\$11,700.00
64	417-0048	90.00	L.F.	Joint Seal Replacement, Type 65W	\$100.00	\$9,000.00	\$135.00	\$12,150.00
65	417-0050	73.00	L.F.	Joint Seal Replacement, Type 100W	\$100.00	\$7,300.00	\$220.00	\$16,060.00
66	417-0070	62.00	L.F.	Headblock Repair, Type 1	\$425.00	\$26,350.00	\$130.00	\$8,060.00
67	417-0071	45.00	L.F.	Headblock Repair, Type 2	\$425.00	\$19,125.00	\$400.00	\$18,000.00
68	417-0073	50.00	S.F.	Spall Repair, Type U	\$100.00	\$5,000.00	\$650.00	\$32,500.00
69	417-0081	602.00	S.F.	Sidewalk, Parapet and Curb Surface Repairs	\$165.00	\$99,330.00	\$120.00	\$72,240.00
70	417-0084	820.00	L.F.	Parapet Reconstruction Location No. 1	\$650.00	\$533,000.00	\$800.00	\$656,000.00
71	417-0089	102.00	L.F.	Parapet Reconstruction, Location No. 2	\$650.00	\$66,300.00	\$1,050.00	\$107,100.00
72	417-0090	770.00	L.F.	Parapet Reconstruction, Location No. 3	\$650.00	\$500,500.00	\$800.00	\$616,000.00
73	417-0091	28.00	L.F.	Parapet Reconstruction Location No. 4	\$650.00	\$18,200.00	\$1,450.00	\$40,600.00
74	417-0108	200,000.00	USD	Force Account for Emergency and Routine Bridge Repairs (No-Bid)	\$1.00	\$200,000.00	\$1.00	\$200,000.00
75	417-N0001	1,950.00	L.F.	Furnishing, Installation and Removal of Temporary Shielding	\$95.00	\$185,250.00	\$440.00	\$858,000.00
76	418-0001	745.00	S.F.	Repair Spalled Concrete, Type 1 - Abutment	\$400.00	\$298,000.00	\$360.00	\$268,200.00
77	418-0002	95.00	S.F.	Repair Spalled Concrete, Type 2 - Abutment	\$410.00	\$38,950.00	\$400.00	\$38,000.00
78	418-0003	50.00	S.F.	Repair Spalled Concrete, Type 2 - Pier	\$425.00	\$21,250.00	\$475.00	\$23,750.00
79	418-0007	1.00	Each	Repair of Structural Steel, Type D	\$9,000.00	\$9,000.00	\$7,000.00	\$7,000.00
80	418-0008	1.00	Each	Repair of Structural Steel, Type E	\$9,000.00	\$9,000.00	\$11,500.00	\$11,500.00
81	418-0009	1.00	Each	Repair of Structural Steel, Type F	\$13,000.00	\$13,000.00	\$15,000.00	\$15,000.00
82	418-0010	1.00	Each	Repair of Structural Steel, Type G	\$8,500.00	\$8,500.00	\$8,000.00	\$8,000.00
83	418-0011	377.00	S.F.	Repair Spalled Concrete, Type 1 - Pier	\$415.00	\$156,455.00	\$430.00	\$162,110.00
84	418-0012	1.00	Each	Repair of Structural Steel, Type H	\$8,000.00	\$8,000.00	\$8,000.00	\$8,000.00
85	418-0013	1.00	Each	Repair of Structural Steel, Type I	\$8,500.00	\$8,500.00	\$11,000.00	\$11,000.00
86	418-0014	1.00	Each	Repair of Structural Steel, Type L	\$8,000.00	\$8,000.00	\$9,000.00	\$9,000.00
87	418-0015	2.00	Each	Repair of Structural Steel, Type M	\$11,000.00	\$22,000.00	\$18,500.00	\$37,000.00
88	418-0016	1.00	Each	Repair of Structural Steel, Type N	\$30,000.00	\$30,000.00	\$30,000.00	\$30,000.00
89	418-0017	2.00	Each	Repair of Structural Steel, Type O	\$6,000.00	\$12,000.00	\$5,500.00	\$11,000.00
90	418-0018	2.00	Each	Repair of Structural Steel, Type P	\$6,000.00	\$12,000.00	\$8,000.00	\$16,000.00
91	418-0019	1.00	Each	Repair of Structural Steel, Type Q	\$25,000.00	\$25,000.00	\$26,000.00	\$26,000.00
92	418-0020	1.00	Each	Repair of Structural Steel, Type R	\$15,000.00	\$15,000.00	\$20,000.00	\$20,000.00
93	418-0024	2,335.00	S.F.	Substructure Waterproofing	\$12.00	\$28,020.00	\$10.00	\$23,350.00
94	418-0028	32.00	Each	Reconstruct Bearing Area	\$7,000.00	\$224,000.00	\$12,000.00	\$384,000.00
95	418-0029	63.00	Each	Repair Bearing	\$8,500.00	\$535,500.00	\$14,000.00	\$882,000.00
96	418-0030	1.00	Each	Reset Bearing	\$9,000.00	\$9,000.00	\$9,000.00	\$9,000.00
97	418-0039	12.00	Each	Replace Anchor Bolt	\$1,500.00	\$18,000.00	\$1,900.00	\$22,800.00
98	418-0051	31.00	Each	Replace Structural Steel Diaphragm	\$11,000.00	\$341,000.00	\$16,000.00	\$496,000.00
99	418-0053	9.00	Each	Temporary Support	\$10,000.00	\$90,000.00	\$12,000.00	\$108,000.00
100	418-0055	330.00	Each	Replace Rivets with High Strength Bolts	\$10.00	\$3,300.00	\$300.00	\$99,000.00
101	418-0056	2.00	Each	Repair of Structural Steel, Type S	\$8,000.00	\$16,000.00	\$18,000.00	\$36,000.00
102	418-0057	1.00	Each	Repair of Structural Steel, Type T	\$12,500.00	\$12,500.00	\$18,000.00	\$18,000.00
103	418-0058	2.00	Each	Repair of Structural Steel, Type U	\$14,000.00	\$28,000.00	\$18,000.00	\$36,000.00
104	418-0059	1.00	Each	Repair of Structural Steel, Type V	\$10,750.00	\$10,750.00	\$13,500.00	\$13,500.00
105	418-0060	1.00	Each	Repair of Structural Steel, Type W	\$5,000.00	\$5,000.00	\$5,000.00	\$5,000.00
106	418-0061	1.00	Each	Repair of Structural Steel, Type X	\$30,125.00	\$30,125.00	\$30,000.00	\$30,000.00
107	418-0062	1.00	Each	Repair of Structural Steel, Type Y	\$14,000.00	\$14,000.00	\$16,000.00	\$16,000.00
108	418-0063	1.00	Each	Repair of Structural Steel, Type Z	\$29,472.00	\$29,472.00	\$40,000.00	\$40,000.00
109	418-0082	1.00	Each	Repair of Structural Steel, Type AA	\$27,000.00	\$27,000.00	\$33,000.00	\$33,000.00
110	418-0083	1.00	Each	Repair of Structural Steel, Type BB	\$17,000.00	\$17,000.00	\$24,500.00	\$24,500.00
111	418-0084	1.00	Each	Repair of Structural Steel, Type CC	\$31,500.00	\$31,500.00	\$28,000.00	\$28,000.00
112	418-0085	1.00	Each	Repair of Structural Steel, Type DD	\$21,750.00	\$21,750.00	\$25,000.00	\$25,000.00
113	418-0086	1.00	Each	Repair of Structural Steel, Type A1	\$12,400.00	\$12,400.00	\$10,000.00	\$10,000.00
114	418-0087	1.00	Each	Repair of Structural Steel, Type A2	\$11,375.00	\$11,375.00	\$15,000.00	\$15,000.00
115	418-0088	1.00	Each	Repair of Structural Steel, Type C1	\$20,125.00	\$20,125.00	\$24,000.00	\$24,000.00
116	418-N0086	5.00	Each	Clean and Paint Bearings	\$2,100.00	\$10,500.00	\$800.00	\$4,000.00
117	499-N0001	1.00	L.S.	Picking Up and Returning Authority Steel Protection Plates	\$10.00	\$10.00	\$2,000.00	\$2,000.00
118	499-N0012	520.00	S.Y.	Thin Polymer Overlay	\$225.00	\$117,000.00	\$260.00	\$135,200.00

BaseLine Item Detail					Ferreira Construction Co. Inc.		Joseph M. Sanzari, Inc.	
Item No.	Unit Code	Qty	UOM	Description	Unit Price	Line Total	Unit Price	Line Total
119	418-N0125	18.00	Each	Temporary Support Type 2	\$12,500.00	\$225,000.00	\$12,000.00	\$216,000.00
120	418-N0126	10.00	Each	Pin and Hanger Repair	\$30,000.00	\$300,000.00	\$30,000.00	\$300,000.00
121	502-0003	70.00	L.F.	18 Inch Half Section HDPE Pipe	\$120.00	\$8,400.00	\$300.00	\$21,000.00
122	503-N0001	4.00	Each	Replace Existing Inlet Grate	\$2,000.00	\$8,000.00	\$1,200.00	\$4,800.00
123	503-N0004	8.00	Each	Reconstruct Inlet, Using Existing Frame, 0ft To 0.5ft Depth	\$2,000.00	\$16,000.00	\$1,500.00	\$12,000.00
124	504-N0004	106.00	S.Y.	Concrete Gutter, 6 Inches Thick	\$475.00	\$50,350.00	\$450.00	\$47,700.00
125	505-0001	2.00	L.F.	Asphalt Concrete Lip Curb	\$400.00	\$800.00	\$550.00	\$1,100.00
126	509-0001	276.00	S.F.	Sign Panels	\$70.00	\$19,320.00	\$63.00	\$17,388.00
127	509-0002	448.00	L.F.	U-channel Post	\$60.00	\$26,880.00	\$54.00	\$24,192.00
128	509-0003	4.00	Each	Removal of Existing Ground-Mounted Sign	\$210.00	\$840.00	\$200.00	\$800.00
129	510-0001	2,414.00	L.F.	Beam Guide Rail	\$48.00	\$115,872.00	\$44.00	\$106,216.00
130	510-0008	100.00	L.F.	Reset Beam Guide Rail	\$25.00	\$2,500.00	\$21.00	\$2,100.00
131	510-0011	1.00	Each	Beam Guide Rail Anchorage	\$2,000.00	\$2,000.00	\$1,700.00	\$1,700.00
132	510-0014	9.00	Each	Parapet Connection, Type A	\$5,500.00	\$49,500.00	\$5,225.00	\$47,025.00
133	510-0015	4.00	Each	Parapet Connection, Type B	\$1,400.00	\$5,600.00	\$1,175.00	\$4,700.00
134	510-0018	3.00	Each	Tangent Guide Rail Terminal	\$5,000.00	\$15,000.00	\$4,175.00	\$12,525.00
135	510-0031	2,890.00	L.F.	Removal of Beam Guide Rail	\$3.00	\$8,670.00	\$1.00	\$2,890.00
136	510-N0076	237.00	Each	Beam Guide Rail Post, 9 FT Long	\$50.00	\$11,850.00	\$47.00	\$11,139.00
137	511-0006	1,410.00	L.F.	Chain Link Fence, Type II, 72in High	\$230.00	\$324,300.00	\$215.00	\$303,150.00
138	511-N0009	30.00	L.F.	Repair Chain Link Fence	\$550.00	\$16,500.00	\$510.00	\$15,300.00
139	516-0001	58,280.00	L.F.	Removable Wet Weather Pavement Marking Tape	\$1.00	\$58,280.00	\$3.00	\$174,840.00
140	516-0005	100.00	L.F.	Striping and Marking Removal, Hydromilling	\$1.00	\$100.00	\$11.00	\$1,100.00
141	516-0006	100.00	L.F.	Striping and Marking Removal, Mechanical	\$1.00	\$100.00	\$11.00	\$1,100.00
142	516-0007	63,020.00	L.F.	Temporary Pavement Striping	\$0.50	\$31,510.00	\$0.50	\$31,510.00
143	516-0008	100.00	L.F.	Traffic Stripes, Long-Life, Epoxy Resin	\$1.50	\$150.00	\$10.00	\$1,000.00
144	516-0009	19,429.00	L.F.	Traffic Stripes, Long-Life, Thermoplastic	\$1.00	\$19,429.00	\$2.00	\$38,858.00
145	516-0011	74.00	L.F.	Traffic Markings, Lines, Long-Life, Thermoplastic	\$2.00	\$148.00	\$2.00	\$148.00
146	516-N0001	80,940.00	L.F.	Removable Black Line Mask, 8in Wide	\$1.00	\$80,940.00	\$4.00	\$323,760.00
147	517-0001	1.00	L.S.	Furnish Field Office, Type A	\$5,000.00	\$5,000.00	\$35,000.00	\$35,000.00
148	517-0007	15.00	Mnth	Maintain Field Office, Type A	\$4,000.00	\$60,000.00	\$4,000.00	\$60,000.00
149	517-0008	15.00	Mnth	Maintain Field Office, Type B	\$4,000.00	\$60,000.00	\$4,000.00	\$60,000.00
150	517-0013	15,000.00	USD	Furnish Office Supplies (No-Bid)	\$1.00	\$15,000.00	\$1.00	\$15,000.00
151	522-0001	20.00	Each	Test Pits	\$750.00	\$15,000.00	\$2,500.00	\$50,000.00
152	524-0003	1.00	Each	Furnishing Temporary Impact Attenuator, Quadguard, 8 Bays, 24in Wide	\$5,000.00	\$5,000.00	\$20,000.00	\$20,000.00
153	524-0062	1.00	Each	Placing and Removing Temporary Impact Attenuator, Quadguard	\$5,000.00	\$5,000.00	\$3,000.00	\$3,000.00
154	524-0063	1.00	Each	Repair Temporary Impact Attenuator, Quadguard	\$2,000.00	\$2,000.00	\$30,000.00	\$30,000.00
155	527-0001	33.00	Each	Utility Support Hangers	\$400.00	\$13,200.00	\$800.00	\$26,400.00
156	530-0001	36.00	Each	Raised Pavement Markers	\$100.00	\$3,600.00	\$60.00	\$2,160.00
157	530-N0001	20.00	Each	Removal of Raised Pavement Markers	\$40.00	\$800.00	\$96.00	\$1,920.00
158	599-N0146	1.00	L.S.	Utility Relocation, Electrical (PSE&G)	\$470,000.00	\$470,000.00	\$1,000,000.00	\$1,000,000.00
159	703-0001	2,156.00	S.Y.	Topsoil	\$18.00	\$38,808.00	\$20.00	\$43,120.00
160	704-0004	2,156.00	S.Y.	Seeding, Type L	\$1.00	\$2,156.00	\$2.00	\$4,312.00
161	706-0001	68.00	S.Y.	Permanent Soil Stabilization Matting	\$60.00	\$4,080.00	\$6.00	\$408.00
162	801-0001	1.00	L.S.	Furnishing Traffic Control Devices	\$290,000.00	\$290,000.00	\$175,000.00	\$175,000.00
163	801-0002	3,000.00	L.F.	Furnishing Precast Concrete Construction Barrier	\$120.00	\$360,000.00	\$50.00	\$150,000.00
164	801-0003	9,900.00	L.F.	Placing and Removing Precast Concrete Construction Barrier	\$5.00	\$49,500.00	\$70.00	\$693,000.00
165	801-0004	400.00	L.F.	Resetting Precast Concrete Construction Barrier	\$5.00	\$2,000.00	\$10.00	\$4,000.00
166	801-0005	3,200.00	L.F.	Modular Glare Screen System	\$1.00	\$3,200.00	\$20.00	\$64,000.00
167	801-0007	1,032.00	M.H.	Traffic Protection Patrol, Part-Time	\$1.00	\$1,032.00	\$100.00	\$103,200.00
168	801-0008	150.00	M.H.	Flaggers	\$22.00	\$3,300.00	\$110.00	\$16,500.00
169	801-0009	8.00	Each	Furnishing Portable Variable Message Sign	\$1.00	\$8.00	\$6,500.00	\$52,000.00
170	801-0013	8.00	Each	Furnishing Truck with Mounted Attenuator	\$200.00	\$1,600.00	\$20,000.00	\$160,000.00
171	801-0014	121.00	M.H.	Furnishing Truck with Mounted Attenuator for Engineer's Use	\$1.00	\$121.00	\$150.00	\$18,150.00
172	801-0015	12.00	Each	Repair Truck Mounted Impact Attenuators	\$500.00	\$6,000.00	\$15,000.00	\$180,000.00
173	801-0016	1.00	L.S.	Picking Up and Returning Authority's Traffic Protection Devices	\$500.00	\$500.00	\$7,000.00	\$7,000.00
174	801-0018	12.00	Each	Furnishing Temporary Impact Attenuator (Array), 70 MPH	\$6,500.00	\$78,000.00	\$12,000.00	\$144,000.00
175	801-0019	28.00	Each	Placing and Removing Temporary Impact Attenuator (Array), 70 MPH	\$250.00	\$7,000.00	\$1,000.00	\$28,000.00
176	801-0020	13.00	Each	Repair and Reset Temporary Impact Attenuator (Array) Module	\$850.00	\$11,050.00	\$1,500.00	\$19,500.00
177	801-N0001	263.00	Each	Installation, Maintenance, and Removal of Lane Closing	\$1.00	\$263.00	\$500.00	\$131,500.00

BaseLine Item Detail					Ferreira Construction Co. Inc.		Joseph M. Sanzari, Inc.	
Item No.	Unit Code	Qty	UOM	Description	Unit Price	Line Total	Unit Price	Line Total
178	803-0001		1.00 L.S.	Maintenance and Protection of Traffic on Location No. 1	\$40,000.00	\$40,000.00	\$172,930.00	\$172,930.00
179	803-0002		1.00 L.S.	Maintenance and Protection of Traffic on Location No. 2	\$40,000.00	\$40,000.00	\$50,000.00	\$50,000.00
180	803-0003		1.00 L.S.	Maintenance and Protection of Traffic on Location No. 3	\$40,000.00	\$40,000.00	\$200,000.00	\$200,000.00
181	803-0004		1.00 L.S.	Maintenance and Protection of Traffic on Location No. 4	\$40,000.00	\$40,000.00	\$30,000.00	\$30,000.00
182	803-0005		1.00 L.S.	Maintenance and Protection of Traffic on Location No. 5	\$40,000.00	\$40,000.00	\$250,000.00	\$250,000.00
183	803-0006		1.00 L.S.	Maintenance and Protection of Traffic on Location No. 6	\$40,000.00	\$40,000.00	\$30,000.00	\$30,000.00
184	803-0007		1.00 L.S.	Maintenance and Protection of Traffic on Location No. 7	\$40,000.00	\$40,000.00	\$30,000.00	\$30,000.00
185	803-0008		1.00 L.S.	Maintenance and Protection of Traffic on Location No. 8	\$40,000.00	\$40,000.00	\$400,000.00	\$400,000.00
186	803-0009		1.00 L.S.	Maintenance and Protection of Traffic on Location No. 9	\$40,000.00	\$40,000.00	\$400,000.00	\$400,000.00
187	803-0032	482,240.00	USD	Police Traffic Directors (No-Bid)	\$1.00	\$482,240.00	\$1.00	\$482,240.00
188	803-N0001		1.00 L.S.	Maintenance and Protection of Traffic on State, County, and Local Roadways	\$21,000.00	\$21,000.00	\$20,000.00	\$20,000.00
189	803-N0004	40,000.00	USD	Local Jurisdiction Escrow (No-Bid)	\$1.00	\$40,000.00	\$1.00	\$40,000.00
190	804-N0001	60,000.00	USD	Railroad Reimbursement Costs (No-Bid)	\$1.00	\$60,000.00	\$1.00	\$60,000.00
						\$17,923,472.00		\$27,317,287.00