

New Jersey Turnpike Authority

P.O. Box 5042, Woodbridge, NJ 07095



January 09, 2026

Document Change Announcement

2016 Standard Supplementary Specifications

Electronic Document Retention

DCA2026SS-01

Subject: Revisions to

Section 107 Prosecution And Progress, Subsection 107.10 Progress Photographs

Section 429 Drilled Shafts, Subsection 429.04 Installation of Drilled Shafts

Section 519 Toll Booths and DATIM Enclosures, Subsection 519.03 Methods of Construction

Description of Change:

These changes consist of removing and modifying language in Authority documents regarding the use of mylar, CDs, DVDs, and thumb/flash drives. This DCA is released in conjunction with DCA2026PM-02. Updates to various files on the Authority's "Supplemental Links" webpage are also made.

Notice to New Jersey Turnpike Authority Staff and Design Consultants

Effective immediately, all contracts currently in the design phase shall incorporate the revisions herein. Contact your New Jersey Turnpike Authority Project Manager for instruction.

The revisions may be accessed on the Authority's webpage: <https://www.njta.com/doing-business/professional-services>

Recommended By:

(signature on original)

Lamis T. Malak, P.E.
Deputy Chief Engineer - Design

(signature on original)

Robert Higham, P.E.
Deputy Chief Engineer - Construction

Approved By:

(signature on original)

Daniel L. Hesslein, P.E.
Chief Engineer

Distribution: Senior Staff Engineering, Law, Operations Depts., UTCA, AGC, All Prequalified Consultant Firms, File

NOTE: All text herein are ADDITIONS to the latest version of the 2016 Standard Supplementary Specifications.

SECTION 107 – PROSECUTION AND PROGRESS

107.10 Progress Photographs

Delete this Subsection in its entirety.

Delete this Subsection in its entirety and replace it with the following:

Before construction operations have started at the site, Contractor shall take and provide color photographs in a number that is sufficient to depict the existing condition of the construction site. A minimum of ten (10) views shall be taken each month to show the progress of work and shall continue until completion of work. The Engineer will determine the actual number and location of views to be taken each month. A complete set of digital image electronic files shall be submitted to the Engineer, without charge to the Authority, promptly after taking the views each month.

The digital files shall be:

- JPEG file format
- Minimum resolution 4032 x 3024 (equivalent to 12 megapixels)
- Identified with the Contract Number, date, and location in the filename

All photographs taken of the construction area shall not be released to any source whatsoever without the prior written permission from the Authority. This provision shall prevail for the duration of the Contract and shall run indefinitely thereafter.

...

SECTION 429 – DRILLED SHAFTS

429.04 Installation of Drilled Shafts

(K) Field Quality Controls

(1) Inspection

Delete item (d) and replace it with the following:

All SID tests shall be recorded on an .mp4 file with audio commentary by the Engineer, identifying the shaft being tested, the test location within the shaft, and the percent of view with sediment thickness greater than ½ inch and 1 ½ inch. Recordings shall be provided to the Authority upon completion of drilled shaft installation.

...

SECTION 519 – TOLL BOOTHS AND DATIM ENCLOSURES

519.03 Methods of Construction

(A) Fabrication

Delete the 2nd paragraph and replace it with the following:

Provide the Authority one PDF set of complete as-built drawings. For each type of toll booth manufactured under the Contract, the Contractor shall furnish one (1) PDF set of as-built specifications, indicating actual materials employed for the toll booths' construction. Drawings shall be provided on 22 by 36-inch sheets. The as-built drawings and specifications shall be furnished to the Engineer at completion of the Project.