ESTIMATE OF QUANTITIES

	ITEM NO.	UNIT CODE	ITEM DESCRIPTION	UNIT	CONTRACT QUANTITY	PLAN SHEET TOTAL	IF AND WHERE DIRECTED	AS BUILT QUANTITY
	1	1D01LAY	CONSTRUCTION LAYOUT	LS	1			
	2	1D10MOB	MOBILIZATION	LS	1			
	3	2B02REX	ROADWAY EXCAVATION, EARTH	CY	17,500	17,500		
⚠	4	2B03REX	ROADWAY EXCAVATION, ROCK	CY	~~8,944~~ 8,404	8,944		
	5	2B05REX	ROADWAY EXCAVATION, MUCK (IF AND WHERE DIRECTED)	CY	1,700		1,700	
⚠	6	2C01EMB	EMBANKMENT, COMMON	CY	~~630~~ 680	~~630~~ 680		
	7	2C02EMB	EMBANKMENT, GRADE A	CY	4,900	4,900		
	8	2E01FEX	FOUNDATION EXCAVATION	CY	210	210		
	9	2F04TEX	TRENCH EXCAVATION, ELECTRICAL	CY	670	670		
	10	2H30TEC	SILT FENCE	LF	300	300		
	11	2H40TEX	INLET FILTERS	EACH	16	16		
	12	2J01DES	DEMOLITION OF EXISTING STRUCTURES, LANES 23 AND 24	LS	1			
	13	2L02SSC	SAWCUTTING	LF	1,775	1,775		
	14	-	REMOVE INLET	EACH	10	10		
	15	-	REMOVE MANHOLE	EACH	4	4		
	16	-	REMOVE PIPE	LF	1,380	1,250	130	
	17	3A07ABC	AGGREGATE BASE COURSE, 6.5" THICK	SY	5,830	5,830		
	18	3B04SUP	SUPERPAVE HOT MIX ASPHALT 12.5H 76 SURFACE COURSE	TON	780	780		
	19	3B11SUP	SUPERPAVE HOT MIX ASPHALT 12.5V 64 INTERMEDIATE COURSE	TON	1,000	1,000		
	20	3B21SUP	SUPERPAVE HOT MIX ASPHALT 25H 64 BASE COURSE	TON	2,340	2,340		
	21	3B26TAC	TACK COAT	GAL	120	120		
	22	3B55APA	ASPHALT PRICE ADJUSTMENT (NO BID)	LS	1			
⚠	23	3C01BRS	BERM SURFACING, 3" THICK	SY	~~850~~ 975	~~850~~ 975		
	24	3D08PCP	PORTLAND CEMENT CONCRETE PAVEMENT, 8" THICK	SY	200	200		
	25	3D10PCP	PORTLAND CEMENT CONCRETE PAVEMENT, 10" THICK	SY	765	765		
	26	3E07PMR	PAVEMENT REMOVAL, 2" DEPTH	SY	920	920		
	27	4A10RFS	REINFORCEMENT STEEL	LBS	9,000	9,000		
	28	4F01GMP	ALUMINUM POSTS FOR GROUND-MOUNTED SIGNS	LBS	710	710		
	29	4F05GMF	CONCRETE FOUNDATIONS FOR GROUND-MOUNTED SIGNS	CY	4	4		
	30	4001TSP	TEMPORARY SHEETING	SF	630	630		
	31	5A01PUD	6-INCH PIPE UNDERDRAIN	LF	1,500	1,500		
⚠	32	5815RC3	15" REINFORCED CONCRETE PIPE	LF	~~35~~ 65	~~35~~ 65		
	33	5B30RC3	30" REINFORCED CONCRETE PIPE	LF	510	510		
	34	5B36RC3	36" REINFORCED CONCRETE PIPE	LF	25	25		
	35	5B48RC3	48" REINFORCED CONCRETE PIPE, CLASS III	LF	500	500		
	36	-	29" x 45" HORIZONTAL ELLIPTICAL REINFORCED CONCRETE PIPE, CLASS III	LF	475	475		
⚠	37	~~5C15RC3~~	~~34" x 53" VERTICAL ELLIPTICAL REINFORCED CONCRETE PIPE, CLASS III~~	~~LF~~	~~35~~	~~35~~		
	38	5C01ND1	INLET, TYPE D1	LF	2	2		
⚠	39	5C01ND2	INLET, TYPE D2	EACH	~~7~~ 9	~~7~~ 9		
	40	5C01ND3	INLET, TYPE D3	EACH	2	2		
	41	-	INLET, TYPE D-2 MODIFIED	EACH	4	4		
	42	-	INLET, TYPE D-3 MODIFIED	EACH	1	1		
	43	5C20NP1	MANHOLE, TYPE P-1	EACH	1	1		
	44	5C20NP2	MANHOLE, TYPE P-2	EACH	2	2		
	45	5C25EP1	RECONSTRUCTED MANHOLE, TYPE P-1, USING EXISTING COVER AND FRAME	EACH	1	1		
	46	5C25EP2	RECONSTRUCTED MANHOLE, TYPE P-2, USING EXISTING COVER AND FRAME	EACH	1	1		
	47	5D10INC	INCIDENTAL CONCRETE (IF AND WHERE DIRECTED)	CY	225		225	
	48	5F01VCA	CONCRETE CURB, TYPE A	LF	1,050	1,050		
	49	-	CONCRETE CURB, TYPE A - MODIFIED	LF	525	525		
	50	5F10SNC	SOLID NOSE	LF	16	16		

0 1/2 1 2 3 4

ORIGINAL SIZE IN INCHES

EQ-1 / EQ-1

No.	DATE	REVISION
⚠	X/XX	ADDENDUM NO. X: REVISED QUANTITIES

	BY	DATE
MADE	XXX	XX-XX-XX
TRACED	XXX	XX-XX-XX
CHECKED	XXX	XX-XX-XX
SUPERVISED	X.XXXX	

No.	DATE	SAMPLE PLAN REVISION
0	5-08	ORIGINAL SHEET

NEW JERSEY TURNPIKE AUTHORITY

ROADWAY NAME

PROJECT DESCRIPTION

CONTRACT NO.

ESTIMATE OF QUANTITIES -1-

NAME OF CONSULTANT
ADDRESS
CERTIFICATE OF AUTHORIZATION NO. XXXXXXXXX

JOHN DOE
NEW JERSEY PROFESSIONAL ENGINEER LICENSE NO. XXXXXXXXXXX

SCALE: NONE
DATE: MAY 2008

4 / 247

FILE NAME: XXXX

ADDENDUM NO. X, SHEET NO. X OF XX