

**New Jersey Turnpike Authority
Engineering Department**

**Order for Professional Services No. P3897
Supervision of Construction Services for
Contract No. P200.568, Drainage Rehabilitation and Sliplining,
Milepost 110.6 to 116.4**

**Responses to Inquiries
Request for Expressions of Interest**

- 1. Inquiry:** The schedule shows a cleaning and video inspection activity, while it is not a pay item on the matrix. I also did not see on the plans cleaning and video inspection other than a quick note on cleaning under No. 6 in the General Notes of construction. Please clarify if cleaning/video storm pipes is part of this contract.

Response: Please see supplementary specification section 502.03 (H) and 502.03 (M), the cleaning and videoing is incidental to the cured in place liner and CCFRPM Slipliner.
- 2. Inquiry:** The plans show headwall repairs. Please confirm that these will be performed under the incidental concrete item. It is usually a headwall or headblock repair item.

Response: Please see Supplementary Specification Section 504.05. The headwall reconstruction and headwall repairs shall be paid for under pay items incidental concrete and reinforcement steel.
- 3. Inquiry:** On Plan Sheet 54 (Drainage and Grading Plan 4) is the RCP to be installed using an open cut across the Parkway mainline?

Response: In some circumstances, open cuts across the mainline are necessary. On Plan Sheet 54 (Drainage and Grading Plan 4) the 24" and 18" RCP are open cut installations. The condition of the existing CMP determines if cured in place liner can be utilized or not. When the condition of the CMP reaches a certain point of deterioration then a complete replacement is necessary.